

2015 BASSETT CREEK RESTORATION PROJECT FOR THE CITY OF GOLDEN VALLEY

Item 5E.
BCWMC 6-18-15
Full plan set online

GOVERNING SPECIFICATIONS

BASSETT CREEK RESTORATION PROJECT SPECIAL PROVISIONS
BASSETT CREEK PLANS
GOLDEN VALLEY GENERAL CONDITIONS
STANDARD SPECIFICATIONS
EDITION OF THE MINNESOTA DEPARTMENT OF
TRANSPORTATION "STANDARD SPECIFICATIONS FOR CONSTRUCTION."

ALL TRAFFIC CONTROL DEVICES AND SIGNING SHALL COMFORM TO THE MN MUTCD INCLUDING THE FIELD MANUAL FOR TEMPORARY TRAFFIC CONTROL ZONE LAYOUTS, DATED JANUARY 2014. ALL TRAFFIC CONTROL DEVICES SHALL HAVE RETROREFLECTIVE SHEETING.

STORM SEWER SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CITY ENGINEERS ASSOCIATION OF MINNESOTA STANDARD UTILITIES SPECIFICATIONS.

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	GENERAL NOTES
3-6	STREAMBANK STABILIZATION DETAILS
7	IMPROVEMENT LOCATION OVERVIEW MAP
8-12	CONSTRUCTION LIMITS & ACCESS MAPS
13-17	CONSTRUCTION PLAN
17-22	EROSION & SEDIMENT CONTROL PLAN
23	STORM SEWER PLAN & PROFILE
24-27	SWPPP NARRATIVE

ALL APPLICABLE FEDERAL, STATE, AND LOCAL LAWS AND ORDINANCES WILL BE COMPLIED WITH IN THE CONSTRUCTION OF THIS PROJECT.

701 Xenia Avenue South, Suite 300
Minneapolis, MN 55416
www.wsbeng.com

763-541-4800 - Fax 763-541-1700
INFRASTRUCTURE ■ ENGINEERING ■ PLANNING ■ CONSTRUCTION

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.

ENGR. _____ PETER R. WILLENBRING
DATE _____ LIC. NO. 15998

PLAN REVIEW:

Prepared for:

City of Golden Valley
7800 Golden Valley Road
Golden Valley, Minnesota 55427
(763)-593-8000

PLAN SYMBOLS

STATE LINE	----
COUNTY LINE	-----
TOWNSHIP OR RANGE LINE	-----
SECTION LINE	-----
QUARTER LINE	-----
SIXTEENTH LINE	-----
RIGHT-OF-WAY LINE	-----
SLOPE EASEMENT	SE
PRESENT RIGHT-OF-WAY	-----
CONTROL OF ACCESS LINE	-----
PROPERTY LINES (EXCEPT LAND LINES)	-----
VACATED PLATTED PROPERTY	-----
CORPORATE OR CITY LIMITS	-----
TRUNK HIGHWAY CENTER LINE	-----
RETAINING WALL	-----
RAILROAD	-----
RAILROAD RIGHT-OF-WAY	-----
RIVER OR CREEK	-----
DRY RUN	-----
DRAINAGE DITCH	-----
DRAIN TILE	-----
CULVERT	-----
DROP INLET	-----
GUARD RAIL	-----
BARBED WIRE FENCE	-----
WOVEN WIRE FENCE	-----
CHAIN LINK FENCE	-----
RAILROAD SNOW FENCE	-----
STONE WALL OR FENCE	-----
HEDGE	-----
RAILROAD CROSSING SIGN	-----
RAILROAD CROSSING BELL	-----
ELECTRIC WARNING SIGN	-----
CROSSING GATE	-----
MEANDER CORNER	-----
SPRINGS	-----
MARSH	-----
TIMBER	-----
ORCHARD	-----
BRUSH	-----
NURSERY	-----
CATCH BASIN	-----
FIRE HYDRANT	-----
CATTLE GUARD	-----
OVERPASS (HIGHWAY OVER)	-----
UNDERPASS (HIGHWAY UNDER)	-----
BRIDGE	-----
BUILDING (ONE STORY FRAME)	-----
F - FRAME C - CONCRETE	-----
S - STONE T - TILE	-----
B - BRICK ST - STUCCO	-----
IRON ROD OR PIPE	-----
MONUMENT (STONE, CONCRETE, OR METAL)	-----
WOODEN HUB	-----
GRAVEL PIT	-----
SAND PIT	-----
BORROW PIT	-----
ROCK QUARRY	-----


UTILITY SYMBOLS

POWER POLE LINE	-----
TELEPHONE OR TELEGRAPH POLE LINE	-----
JOINT TELEPHONE AND POWER ON POWER POLE	-----
ON TELEPHONE POLES	-----
ANCHOR	-----
STREET LIGHT	-----
PEDESTAL (TELEPHONE CABLE TERMINAL)	-----
GAS MAIN	-----
WATER MAIN	-----
CONDUIT	-----
TELEPHONE CABLE IN CONDUIT	-----
ELECTRIC CABLE IN CONDUIT	-----
TELEPHONE MANHOLE	-----
ELECTRIC MANHOLE	-----
BURIED TELEPHONE CABLE	-----
BURIED ELECTRIC CABLE	-----
AERIAL TELEPHONE CABLE	-----
SEWER (SANITARY OR STORM)	-----
SEWER MANHOLE	-----

SCALES

INDEX MAP	0 500 1000
PLAN	0 30 60
PROFILE HORIZ.	0 30 60
VERT.	0 5 10

CONSTRUCTION PLAN FOR: STREAMBANK STABILIZATION AND HABITAT RESTORATION LOCATED ON BASSETT CREEK
PROJECT LOCATION: RHODE ISLAND AVE TO DULUTH STREET



THE INFORMATION SHOWN ON THESE DRAWINGS CONCERNING TYPE AND LOCATION OF PRIVATE UTILITIES IS NOT GUARANTEED TO BE ACCURATE OR ALL-INCLUSIVE. THE CONTRACTOR IS TO DETERMINE THE TYPE AND LOCATION OF PRIVATE UTILITIES AS MAY BE NECESSARY TO AVOID DAMAGE THERETO. SUBSURFACE UTILITY INFORMATION IN THIS PLAN IS UTILITY QUALITY LEVEL D. THIS QUALITY LEVEL WAS DETERMINED ACCORDING TO THE GUIDELINES OF CI/ASCE 38-2, ENTITLED "STANDARD GUIDELINES FOR THE COLLECTION AND DEDICATION OF EXISTING SUBSURFACE UTILITY DATA."

EXCAVATION NOTICE SYSTEM

A CALL TO GOPHER STATE ONE (651-454-0002) IS REQUIRED A MINIMUM OF 48 HOURS PRIOR TO PERFORMING ANY EXCAVATION.

SPECIAL NOTE

THE PLANS OUTLINED HEREIN GENERALLY DESCRIBE THE PROPOSED IMPROVEMENTS FOR THE MAIN STEM OF BASSETT CREEK RESTORATION PROJECT. AS PART OF CONSTRUCTION FOR THESE PROPOSED IMPROVEMENTS, THE CONTRACTOR IS EXPECTED TO WORK CLOSELY, IN THE FIELD, WITH THE OWNERS REPRESENTATIVE REGARDING THE FINAL EXTENT AND LOCATION TO WHICH THE PROPOSED IMPROVEMENTS ARE INSTALLED. THIS COORDINATION SHOULD BE INCLUDED WITH THE UNIT BID PRICES.

SITE ACCESS

SITE ACCESS AND LIMITS OF CONSTRUCTION ARE IDENTIFIED ON THE PLANS. ACTUAL ACCESS ROUTES AND LIMITS OF CONSTRUCTION WILL BE STAKED IN THE FIELD BY THE ENGINEER. CONTRACTOR MAY OBTAIN ADDITIONAL ACCESS AT THEIR OWN EXPENSE.

GENERAL CONSTRUCTION NOTES

- CONTRACTOR IS RESPONSIBLE TO LOCATE AND FIELD VERIFY ALL EXISTING UTILITIES PRIOR TO WORK.
- EXISTING ROADS, PARKING LOTS, TRAILS, FENCES SIGNS, UTILITIES, IRRIGATION SYSTEMS AND ALL OTHER ASSOCIATED AND EXISTING FACILITY SITE FEATURES SHALL BE PROTECTED DURING CONSTRUCTION. CONTRACTOR IS RESPONSIBLE FOR REPAIRING ALL DAMAGE THAT OCCURS TO EXISTING FACILITIES.
- CONTRACTOR SHALL INSTALL ALL EROSION CONTROL BMPS PRIOR TO COMMENCEMENT OF GRADING.
- ALL TREES WITH A DIAMETER OF 4 INCHES OR LARGER SHALL BE MARKED FOR REMOVAL BY OWNER OR OWNER'S REPRESENTATIVE. TREES REMOVED THAT ARE NOT MARKED SHALL BE REPLACED IN KIND AT CONTRACTORS EXPENSE.
- ALL DISTURBED AREAS MUST BE TEMPORARILY STABILIZED WITHIN 48 HOURS OF INACTIVITY.
- ALL GROUND DISTURBANCE GENERATED BY GRADING ACTIVITIES SHALL BE STABILIZED AND RESTORED BY FINISH GRADING WITH TOPSOIL, APPLYING NATIVE SEED W/COVER CROP AND EROSION CONTROL BLANKET INCLUDING ACCESS ROUTES AND STOCKPILE
- SEED BED SHALL BE PREPARED WITH A MINIMUM OF 4 INCHES OF TOPSOIL WITH NO EXTRANEIOUS MATERIAL OVER ¼ INCHES ON THE SURFACE.
- EROSION CONTROL BLANKET SHALL BE MNDOT CATEGORY 4 OR OTHERWISE AS SPECIFIED.
- VEGETATIVE AND BIOENGINEERING SOLUTIONS SHALL BE INCORPORATED WHEREVER APPROPRIATE AND FEASIBLE.

RECOMMENDED CONSTRUCTION SEQUENCE

- PROVIDE TRAFFIC CONTROL SIGNS AS NEEDED
- INSTALL SILT CURTAIN AND OTHER SEDIMENT CONTROLS
- REMOVE SELECTED TREES AND STUMPS AS MARKED AND DIRECTED IN THE FIELD BY THE ENGINEER
- STRIP IN PLACE TOPSOIL IN AREAS TO BE DISTURBED AND STOCKPILE.
- SHAPE AND GRADE CHANNEL BANKS TO PROPOSED TYPICAL SECTION (3:1 SLOPES MAX FROM EXISTING TOE OF BANK)
- INSTALL SELECTED STREAMBANK STABILIZATION METHOD IDENTIFIED WITHIN THE PLANS (SEE DETAILS)
- FINISH GRADE DISTURBED AREAS, SPREAD TOPSOIL, SEED, AND STABILIZE WITH SELECTED METHOD
- INSTALL CATEGORY 4 EROSION CONTROL BLANKET (ON SLOPES STEEPER THAN 4:1) OR STRAW MULCH OVER DISTURBED AREAS
- REMOVE SILT CURTAIN, OTHER SEDIMENT CONTROLS AND ANY MISCELLANEOUS DEBRIS THAT WAS REMOVED FROM THE CHANNEL

TREE AND STUMP REMOVAL NOTE

THE ENGINEER WILL SELECT THE TREES AND STUMPS THAT ARE TO BE REMOVED TO GAIN ACCESS TO AND TO PROVIDE THE REQUIRED MAINTENANCE AREAS. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF THE TREES, BRUSH, STUMPS, AND ROOTS FROM THE AREA DESIGNATED FOR CLEARING AND GRUBBING.

UTILITY COORDINATION AND CONFLICT:

UTILITY LOCATE INFORMATION IS LOCATED IN AN A APPENDIX OF THE SPECIFICATIONS AND NOT SHOWN ON THE PLANS. THE CONTRACTOR SHALL SCHEDULE OR REDIRECT HIS/HER WORK TO ENSURE THAT UTILITY COMPANY RELOCATES, INSTALLATIONS AND/OR REMOVALS DO NOT IMPEDE PROGRESS OF THE PROJECT. THE CONTRACTOR SHALL ALSO COORDINATE ALL UNANTICIPATED UTILITY RELOCATIONS OR ADJUSTMENTS DETERMINED TO BE NECESSARY TO COMPLETE THE WORK. NO CLAIMS FOR EXTRA COMPENSATION TO PERFORM THE WORK IN ACCORDANCE WITH THE PLANS THAT ARE DUE TO CONFLICTS WITH IN-PLACE UTILITIES SHALL BE CONSIDERED.

CONTRACTOR RESPONSIBILITY

CONTRACTOR IS RESPONSIBLE TO PROTECT THE PROJECT AREA, INCLUDING AREAS THAT HAVE BEEN RESTORED AND AREAS THAT HAVE NOT BEEN COMPLETED, CONSTRUCTION EQUIPMENT, AND CONSTRUCTION MATERIALS DURING ADVERSE WEATHER CONDITIONS AND PERIODS OF HIGH FLOWS WITHIN THE CHANNEL AT ALL TIMES. NO COMPENSATION WILL BE MADE TO THE CONTRACTOR FOR ADDITIONAL COSTS INCURRED FOR REPAIR OR REPLACEMENT OF ANY DAMAGE THAT MAY OCCUR DUE TO ADVERSE WEATHER CONDITIONS.

SEEDING SPECIFICATIONS:

SEEDING NATIVE GRASSES

RESHAPED AND DISTURBED AREAS ALONG BASSETT CREEK WILL BE REESTABLISHED WITH THE FOLLOWING:

- SEED MIX(S)** PRAIRIE RESTORATION INC. (PRI) SHORELINE GRASS MIX OR SAVANNA GRASS MIX TO BE APPLIED AT @ 20 LBS/AC.
- THE **PRI SHORELINE SEED** MIX IS A SHADE TOLERANT MIX THAT IS ABLE TO WITHSTAND INUNDATION FOR SEVERAL DAYS. THE **PRI SHORELINE SEED** MIX WILL BE USED ALONG THE DISTURBED SLOPES OF BASSETT CREEK FROM THE TOP OF STONE TO THE APPROXIMATE 10 YEAR STAGE ELEVATION, TO BE STAKED IN THE FIELD.
- THE **PRI SAVANNA SEED** MIX IS A SHADE TOLERANT MIX THAT IS SUITABLE FOR UPLAND AREAS. THE **PRI SAVANNA SEED** MIX WILL BE USED ALONG THE DISTURBED SLOPES OF BASSETT CREEK FROM THE APPROXIMATE 10 YEAR STAGE ELEVATION TO THE TOP OF SLOPE, TO BE STAKED IN THE FIELD.
- THE PLACEMENT OF THESE SEED MIXES WILL BE DIRECTED BY THE ENGINEER IN THE FIELD
- ADDITIONAL TEMPORARY SEED:** ADDITIONAL OATS OR WINTER WHEAT SHALL BE MIXED INTO PRI MIXES @ 50 LBS/AC TO PROVIDE A FAST GROWING VEGETATIVE COVER.

DESCRIPTION OF PROPOSED IMPROVEMENTS

THE TECHNIQUES DISCUSSED BELOW ARE COMMONLY USED IN STREAMBANK RESTORATION . THEY WERE INCLUDED IN THE DESIGN FOR THEIR FUNCTIONALITY WITH THE EXPECTATION THAT MOST CONTRACTORS HAVE HAD EXPERIENCE WITH THESE TECHNIQUES AND UNDERSTAND HOW TO INSTALL THEM. THIS DESIGN INCORPORATES THE MOST APPROPRIATE MEASURES TO USE AT EACH INDIVIDUAL SITE IN ORDER TO MEET THE STABILIZATION OBJECTIVES . THE FINAL SIZE, DEPTH, AND LOCATION OF THESE BMPs SHALL BE FINALIZED IN THE FIELD, BY THE PROJECT AND FIELD ENGINEER, DURING CONSTRUCTION. IT SHOULD BE NOTED THAT EARTHWORK FOR THIS PROJECT WILL LIKELY NOT BALANCE AND THAT IMPORTED MATERIALS WILL REQUIRE AN EQUAL (OR NEAR EQUALL VOLUME OF MATERIAL REMOVED.

SLOPE SHAPING

THIS WORK CONSISTS OF SHAPING THE CONTOURS OF THE MAINTENANCE AREAS TO ACHIEVE SLOPES AS SHOWN ON THE PLANS. SLOPE PREPARATION WILL AID IN THE PLACEMENT OF THE SELECTED SLOPE STABILIZATION METHOD. IT IS ANTICIPATED THAT EARTHWORK ON THIS PROJECT WILL BALANCE ON SITE (SEE DETAIL). CONTRACTOR TO BALANCE MATERIALS ON SITE TO THE MAXIMUM EXTENT FEASIBLE. IN AREAS WHERE MATERIAL CANNOT BE BALANCED ON SITE, THE EXCESS MATERIAL SHALL BE REMOVED AND PAID FOR BY THE COMMON EXCAVATION CONTRACT ITEM.

FIELDSTONE BOULDER

FIELDSTONE BOULDER WILL BE USED TO PROTECT THE TOE OF THE STREAM BANK. IN STREAM TYPICALLY CONSISTS OF BOULDER-SIZED ROCK (30 INCHES TO 34 INCHES IN DIAMETER) PLACED OVER A HALF FOOT THICK LAYER OF CLASS I FIELDSTONE RIP RAP AND A HALF FOOT LAYER OF COARSE FILTER AGGREGATE. THE BOULDER WILL EXTEND UP THE RESHAPED SLOPE AND CANNOT EXTEND PAST THE TOP OF BANK. THE EXACT LOCATION AND ELEVATION OF THE BOULDER TOE WILL BE STAKED IN THE FIELD BY THE ENGINEER(SEE DETAIL). **PLACEMENT OF FIELDSTONE BOULDERS MUST NOT RESULT IN A DECREASE OF CHANNEL CROSS SECTION.**

FIELDSTONE RIP RAP

FIELDSTONE RIP RAP WILL BE USED TO PROTECT THE TOE OF THE STREAM BANK. IN STREAM SYSTEMS, RIP RAP CONSISTS OF COBBLE-SIZED ROCK (12 INCHES TO 18 INCHES IN DIAMETER). THE RIPRAP IS KEYED IN TO THE STREAMBED AND EXTENDS UP THE RESHAPED SLOPE AND CANNOT EXTEND PAST THE TOP OF BANK. THE EXACT LOCATION AND ELEVATION OF THE STONE TOE WILL BE STAKED IN THE FIELD BY THE ENGINEER. HAND PLACEMENT OF FIELDSTONE RIP RAP WILL BE REQUIRED AND WILL BE DIRECTED BY THE ENGINEER (SEE DETAIL). **PLACEMENT OF FIELDSTONE RIP RAP MUST NOT RESULT IN A DECREASE OF CHANNEL CROSS SECTION.**

LIVE STAKES

LIVE STAKES ARE DORMANT STEM CUTTINGS, TYPICALLY WILLOW AND DOGWOOD SPECIES. THEY ARE COLLECTED AND INSTALLED DURING THE DORMANT SEASON AND GROW NEW ROOTS AND LEAVES REVEGETATING A STREAM BANK. MATERIALS WILL BE CUT AND PLACED IN A CONTAINER OF WATER TO BE TRANSPORTED TO THE SITE AND KEPT IN WATER UNTIL INSTALLED. TAPER THE CUTTING WITH THE END GOING INTO THE GROUND AT RIGHT ANGLES TO THE SLOPE FACE, 2/3 - 3/4 OF THEIR LENGTH. CARE SHALL BE TAKEN NOT TO SPLIT THE ENDS OR DAMAGE THE BARK OF THE CUTTINGS. THE ENGINEER SHALL STAKE THE LOCATION OF LIVE STAKES IN THE FIELD (SEE DETAIL).

SOIL STABILIZATION REQUIREMENTS FOR SEEDING NATIVE GRASSES:

- STRAW MULCH** @ 2 TON/AC (SLOPES LESS THAN 4:1)
- BLANKET** MNDOT TYPE IV FOR (SLOPES GREATER THAN 4:1)
- THE PLACEMENT OF SOIL STABILIZATION MEASURES WILL BE DIRECTED BY THE ENGINEER IN THE FIELD.

TURF ESTABLISHMENT

AREAS DISTURBED DURING CONSTRUCTION THAT ARE NOT IMMEDIATELY ADJACENT TO BASSETT CREEK OR IN NON-MAINTAINED AREAS SHALL BE REESTABLISHED WITH THE FOLLOWING:

- SEED MIX** MNDOT 260 @ 100 LBS/AC
- FERTILIZER** MNDOT TYPE 2 @ 200 LBS/AC
- STRAW MULCH** @ 2 TON/AC AND DISC ANCHORED MULCHED (SLOPES LESS THAN 4:1)
- EROSION BLANKET** MNDOT TYPE 4 FOR (SLOPES GREATER THAN 4:1)
- AREAS REQUIRING TURF ESTABLISHMENT WILL BE DIRECTED BY THE ENGINEER IN THE FIELD AND INCLUDE EITHER TYPE I MULCH MATERIAL OR CATEGORY 4 EROSION CONTROL BLANKET.


I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA
PETER R. WILLENBRING, PROFESSIONAL ENGINEER
DATE: _____ LIC. NO. 1598B

2015 MAIN STEM OF BASSETT CREEK RESTORATION PROJECT
CITY OF GOLDEN VALLEY


701 Xenia Avenue South, Suite 300
Minneapolis, MN 55416
www.wsbeng.com
WSB & Associates, Inc.
INFRASTRUCTURE ENGINEERING | PLANNING | CONSTRUCTION

K:\02032-090\Cad\Proposed\02032-090 - Edgewood Storm.dwg


RIP RAP TOE STABILIZATION



BOULDER WALL SECTION



BIOLOG & BOULDER TOE SECTION



CONSTRUCTION NOTES:

1. NO NET CUT/FILL ALLOWED WITHIN CHANNEL CROSS SECTION, EXISTING CHANNEL SECTION AREA MUST BE MAINTAINED. FILL VOLUMES RESULTING FROM BOULDERS, AGGREGATE, AND OTHER MATERIALS BROUGHT IN FOR STABILIZATION WILL BE OFFSET WITH AN EQUAL VOLUME OF COMMON EXCAVATION. SEE SPECIFICATIONS FOR MORE INFORMATION ON COMMON EXCAVATION. THE OVERALL EARTHWORK WILL LIKELY NOT BALANCE AND THAT IMPORTED ROCK AND OTHER MATERIAL WILL REQUIRE AN EQUAL AMOUNT OF EXCAVATION.

2. ALL IMPROVEMENTS SHALL FOLLOW THE MEANDERS AND CURVES OF THE EXISTING STREAMBANK AS INDICATED ON PLANS AND AS STAKED/DIRECTED IN THE FIELD. ALL PREEXISTING POOLS AND RIFFLES SHALL BE PROTECTED AND MAINTAINED.

3. EACH AREA (A THROUGH E) TO BE INSPECTED AND REVIEWED BY OWNER AND ENGINEER FOLLOWING CONSTRUCTION TO ENSURE PROPER INSTALLATION.

4. QUANTITIES FOR MATERIALS USED IN EACH CONSTRUCTION AREA WILL BE TABULATED AND AGREED UPON PRIOR TO BEGINNING CONSTRUCTION IN EACH AREA.


5. DUE TO UNCERTAINTY IN MATERIAL DELIVERY QUANTITIES AND WEIGHTS, A RANGE OF ACCEPTABLE QUANTITIES MAY BE AGREED UPON PRIOR TO CONSTRUCTION IN EACH AREA. CONTRACTOR MAY NOT INSTALL ANY QUANTITIES IN EXCESS OF PLANNED OR AGREED UPON NUMBERS WITHOUT FIRST CONSULTING THE ENGINEER.

6. FINAL HEIGHTS OF IMPROVEMENTS TO BE STAKED IN THE FIELD BY THE ENGINEER. SEE THE PLANS FOR APPROXIMATE ELEVATIONS FOR TOP OF IMPROVEMENTS.


APPROXIMATE ELEVATIONS

AREA	TOP OF BANK	NWL
A	882	878
B	881	867
C	868 - 870	864 - 867
D	865-866; 862 in sinuous, meandering area	858 - 863
E	860-862	856 - 858


VEGETATED BENCH SECTION




BIOLOG & STONE TOE SECTION




VEGETATED BENCH PLAN VIEW



BIOLOG & STONE TOE PLAN VIEW



SLOPE SHAPING DETAIL



I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA

PETER R. WILLENBRING, PROFESSIONAL ENGINEER

DATE: _____ LIC. NO. 15998




2015 MAIN STEM OF BASSETT CREEK RESTORATION PROJECT
CITY OF GOLDEN VALLEY

701 Xenia Avenue South, Suite 300
Minneapolis, MN 55416
www.wsbeng.com

763-541-4800 • Fax 763-541-1100

WSB & Associates, Inc.
INFRASTRUCTURE ENGINEERING | PLANNING | CONSTRUCTION

K:\02032-09\Cad\Proposed\02032-090 - Edgewood Storm.dwg




REVISION NO.	DATE	EXPLANATION
SCALE:	AS NOTED	
PLAN BY:	JHA	
DESIGN BY:	JHA	
CHECKED BY:	PRW	
PROJECT NO.	02032-09	
DATE		
RECORD COPY BY:		
<small>I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA</small>		
<small>PETER R. WILLENBRING, PROFESSIONAL ENGINEER</small>		
DATE:	LIC. NO.:	15998

2015 MAIN STEM OF BASSETT CREEK RESTORATION PROJECT
CITY OF GOLDEN VALLEY



WSB & Associates, Inc.
INFRASTRUCTURE | ENGINEERING | PLANNING | CONSTRUCTION

701 Xenia Avenue South, Suite 300
 Minneapolis, MN 55416
 www.wsbeng.com
 763-541-4800 • Fax 763-541-1700


K:\02032-09\Cad\Proposed\02032-090 - Edgewood Storm.dwg



FLOATING SILT CURTAIN DETAIL






EROSION CONTROL BLANKET INSTALLATION DETAIL



1. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED.
2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN A 6" (15cm) DEEP X 6" (15cm) WIDE TRENCH WITH APPROXIMATELY 12" (30cm) OF BLANKET EXTENDED BEYOND THE UP-SLOPE PORTION OF THE TRENCH. ANCHOR THE BLANKET WITH A ROW OF STAPLES/STAKES APPROXIMATELY 12" (30cm) APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 12" (30cm) PORTION OF BLANKET BACK OVER SEED AND COMPACTED SOIL. SECURE BLANKET OVER COMPACTED SOIL WITH A ROW OF STAPLES/STAKES SPACED APPROXIMATELY 12" (30cm) APART ACROSS THE WIDTH OF THE BLANKET.
3. ROLL THE BLANKETS (A.) DOWN OR (B.) HORIZONTALLY ACROSS THE SLOPE. BLANKETS WILL UNROLL WITH APPROPRIATE SIDE IN APPROPRIATE LOCATIONS AS SHOWN IN THE STAPLE PATTERN GUIDE. WHEN USING OPTIONAL DOT SYSTEM, STAPLES/STAKES SHOULD BE PLACED THROUGH EACH OF THE COLORED DOTS CORRESPONDING TO THE APPROPRIATE STAPLE PATTERN.
4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2"-5" (5cm-12.5cm) OVERLAP DEPENDING ON BLANKET TYPE. TO ENSURE PROPER SEAM ALIGNMENT, PLACE THE EDGE OF THE OVERLAPPING BLANKET (BLANKET BEING INSTALLED ON TOP) EVEN WITH THE COLORED SEAM STITCH ON THE PREVIOUSLY INSTALLED BLANKET.
5. CONSECUTIVE BLANKETS SPLICED DOWN THE SLOPE MUST BE PLACED END OVER END (SHINGLE STYLE) WITH AN APPROXIMATE 3" (7.5cm) OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" (30cm) APART ACROSS ENTIRE BLANKET WIDTH.

NOTE:
*IN LOOSE SOIL CONDITIONS, THE USE OF STAPLE OR STAKE LENGTHS GREATER THAN 6" (15cm) MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.



K:\02032-09\Cad\Proposed\02032-090 - Edgewood Storm.dwg



**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**


Improvement Locations

Legend

- █ Area A
- █ Area B
- █ Area C
- █ Area D
- █ Area E
- Creek Stationing



0 250 500 1,000 Feet




- Contractor to restore all access points, staging locations, and haul roads to pre-project conditions.
 - Disturbed areas within 15' of bank to be reseeded with native vegetation; other disturbed areas to be restored to pre-project conditions to the maximum extent practicable.




2015 Bassett Creek Main Stem Restoration Project
 City of Golden Valley
 Minnesota

Construction Zone and Access
 Area A



Legend

- Staging
- Parcels
- 20' Construction Zone and Access
- Creek Edge
- Proposed Grading Limits
- Creek Stationing
- Preferred Access



**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**

**Construction Zone and Access
Area B**


Legend


- Access Route
- Staging
- Parcels
- 20' Construction Zone and Access
- Creek Edge
- Proposed Grading Limits
- Creek Stationing
- Preferred Access



0 25 50 100 Feet

- Contractor to restore all access points, staging locations, and haul roads to pre-project conditions.
- Disturbed areas within 15' of bank to be reseeded with native vegetation; other disturbed areas to be restored to pre-project conditions to the maximum extent practicable.





- Contractor to restore all access points, staging locations, and haul roads to pre-project conditions.
 - Disturbed areas within 15' of bank to be reseeded with native vegetation; other disturbed areas to be restored to pre-project conditions to the maximum extent practicable.




2015 Bassett Creek Main Stem Restoration Project
 City of Golden Valley
 Minnesota

Construction Zone and Access
 Area C

Legend

- Staging
- Parcels
- 20' Construction Zone and Access
- Creek Edge
- Proposed Grading Limits
- Creek Stationing
- Preferred Access




- Contractor to restore all access points, staging locations, and haul roads to pre-project conditions.
 - Disturbed areas within 15' of bank to be reseeded with native vegetation; other disturbed areas to be restored to pre-project conditions to the maximum extent practicable.




2015 Bassett Creek Main Stem Restoration Project
 City of Golden Valley
 Minnesota

Construction Zone and Access
 Area D




Legend

- Staging
- Parcels
- 20' Construction Zone and Access
- Creek Edge
- Proposed Grading Limits
- Creek Stationing
- Preferred Access



- Contractor to restore all access points, staging locations, and haul roads to pre-project conditions.
 - Disturbed areas within 15' of bank to be reseeded with native vegetation; other disturbed areas to be restored to pre-project conditions to the maximum extent practicable.




**2015 Bassett Creek Main Stem
 Restoration Project
 City of Golden Valley
 Minnesota**

**Construction Zone and Access
 Area E**

Legend


- Staging
- Parcels
- 20' Construction Zone and Access
- Creek Edge
- Proposed Grading Limits
- Creek Stationing
- Preferred Access





2015 Bassett Creek Main Stem Restoration Project
City of Golden Valley
Minnesota

Construction Plans
Area A



Contractor to plant live stakes along length of restored sections, as staked in the field, in the following proportions:
2/3 dogwood, 1/3 willow

Sta 8+00:
- Remove existing gabions at culvert
- Remove grouted rip rap
- Place 30 tons of class III rip rap at culverts

Sta 4+50 to 6+50, Left:
Do not shape back bank

Remove debris from channel in this location as directed by engineer in the field

Protect 18" HDPE

Sta 3+25 to 8+00
Stabilize steep sections with Vegetated bench in areas where shaping not feasible

Protect 12" RCP

Protect 21" RCP

Sta 0+50 to 8+00
- Stabilize Streambanks with 12" Biolog and stone toe

Remove debris from channel in this location as directed by engineer in the field

Tree Removals:
Sta 0+00 to 8+00
- Remove approximately 50 trees
- Clear dead, dying, and leaning trees
- Clear brush along streambank
- Clearing shall be limited to the maximum extent feasible. Final clearing limits to be staked and directed in the field by the Engineer.

Legend

- Storm Sewer
- Vegetated Bench
- Biolog with Stone Toe
- Parcels
- Creek Stationing



0 15 30 60 Feet



**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**


**Construction Plans
Area B**

Legend

- Storm Sewer
- Vegetated Bench
- Biolog with Stone Toe
- Parcels
- Creek Stationing



0 15 30 60 Feet





**2015 Bassett Creek Main Stem Restoration Project
City of Golden Valley
Minnesota**


**Construction Plans
Area C**

Legend

- Storm Sewer
- Rip Rap Toe Stabilization
- Boulder Wall
- Previously Stabilized
- Vegetated Bench
- Biolog with Stone Toe
- Parcels
- Creek Stationing



0 40 80 160 Feet



Contractor to plant live stakes along length of restored sections, as staked in the field, in the following proportions:
2/3 dogwood, 1/3 willow

Station 46+75 to 47+25:
- Stabilize north bank with vegetated bench

Sta 50+90
- Place 48" manhole in existing alignment, 10' back from bank
- MH to have 4' sump
- Install 15 feet of 12" RCP at 45 degrees (towards downstream) from existing alignment.
- Stabilize outfall with class II rip rap
- Install 12" RCP FES at 869.62 (field verify)
- Install sheet piling per details.
(see details on sheets 2-6)

Station 55+00 to 57+00:
- Stabilize with vegetated bench
- Top of bench section at approximately 868.00 (field verify)

Protect 16" HDPE and protect emergency overflow from pond

Station 58+75:
- Protect 15" PVC

Sta 48+00 to 53+50
Stabilize streambanks with fieldstone rip rap toe stabilization and limited slope shaping

Coordinate work near culverts with Douglas Drive reconstruction project managers.

Sta 42+50 to 45+50 (both banks);
Sta: 46+75 to 47+25 (south bank):
- Stabilize using 12" biolog with stone toe

Sta 54+50 to 58+70
Stabilize Streambanks with 12" Biolog with Stone Toe

Sta 58+70 to 59+70:
- Stabilize north and south banks with 6 ft fieldstone boulder wall on the upbank side of the timber bridge piers.
- Top of boulders at approximately 871.00 (field verify)
- Transition downstream ends into existing banks to reduce scour
- Boulder walls must be built into the existing bank and must not constrict the channel in this location.

Sta 54+50 to 55+25, Right
- Do not shape slope back

Station 46+75 to 47+25:
- Clear fallen tree on north bank
- Clear buckthorn on south bank

Remove large tree constricting channel

Remove Box Elder immediately west of bridge.

Tree Removals:
Sta 48+00 to 53+00
- Remove approximately 25 trees, mostly buckthorns
- Apply herbicide treatment to buckthorns
- Clear dead, dying, and leaning trees
- Clear brush along streambank
- Clearing shall be limited to the maximum extent feasible. Final clearing limits to be staked and directed in the field by the Engineer.

Tree Removals:
Sta 42+00 to 47+00
- Remove approximately 25 trees
- Clear dead, dying, and leaning trees
- Clear brush along streambank
- Clearing shall be limited to the maximum extent feasible. Final clearing limits to be staked and directed in the field by the Engineer.

Tree Removals:
Sta 55+00 to 59+00
- Remove approximately 35 trees
- Clear dead, dying, and leaning trees
- Clear brush along streambank
- Clearing shall be limited to the maximum extent feasible. Final clearing limits to be staked and directed in the field by the Engineer.





**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**

**Construction Plans
Area D**


Legend

- Storm Sewer
- Boulder Wall
- Previously Stabilized
- Biolog with Boulder Toe
- Parcels
- Creek Stationing

NOTE: The predominant restoration practice in this reach is the biolog and boulder toe. Other stabilization practices will be considered within this reach -- as topography and other conditions allow -- as directed in the field by the Engineer.



0 30 60 120 Feet





**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**


**Construction Plans
Area E**

Legend

- Storm Sewer
- Previously Stabilized
- Vegetated Bench
- Biolog with Stone Toe
- Parcels
- Creek Stationing




0 35 70 140 Feet






**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**

**Erosion & Sediment Control
Area A**




Legend

- Rock Construction Entrance
- Silt Fence
- Floating Silt Fence
- Staging
- Parcels
- Creek Stationing
- Preferred Access



**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**

**Erosion & Sediment Control
Area B**



Legend

- Rock Construction Entrance
- Silt Fence
- Floating Silt Fence
- Staging
- Parcels
- Creek Stationing
- Preferred Access




0 25 50 100 Feet



**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**

**Erosion & Sediment Control
Area C**



Legend

-  Rock Construction Entrance
-  Silt Fence
-  Floating Silt Fence
-  Staging
-  Parcels
-  Creek Stationing
-  Preferred Access



0 25 50 100 Feet



**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**


**Erosion & Sediment Control
Area D**

Legend

-  Rock Construction Entrance
-  Silt Fence
-  Floating Silt Fence
-  Staging
-  Parcels
-  Creek Stationing
-  Preferred Access




0 25 50 100 Feet





**2015 Bassett Creek Main Stem
Restoration Project
City of Golden Valley
Minnesota**

**Erosion & Sediment Control
Area E**



Legend

-  Rock Construction Entrance
-  Silt Fence
-  Floating Silt Fence
-  Staging
-  Parcels
-  Creek Stationing
-  Preferred Access



0 25 50 100 Feet



STORMWATER POLLUTION PREVENTION PLAN (SWPPP) NARRATIVE

PROJECT SITE EVALUATION, ASSESSMENT, AND PLANNING

THIS NARRATIVE IS TO SERVE AS A GUIDANCE PLAN AND MUST BE AMENDED AND MODIFIED AS SITE CONDITIONS CHANGE DURING CONSTRUCTION.

PROJECT LOCATION/DESCRIPTION

PROJECT/SITE NAME: BASSETT CREEK 2015 RESTORATION
 PROJECT NUMBERS: WSB #02032-09
 PROJECT LOCATION: STREET: LEWIS RD, DULUTH ST, VALE CREST ROAD CITY/TOWNSHIP: GOLDEN VALLEY COUNTY: HENNEPIN STATE: MINNESOTA ZIP: 55422
 LATITUDE/LONGITUDE: 44.9931/-93.3602

CONTACT INFORMATION/RESPONSIBLE PARTIES

THE CITY OF GOLDEN VALLEY OWNS THE LAND, ADJACENT ROADS, AND EASEMENT AREAS ASSOCIATED WITH THE PROJECT. THE CITY OF GOLDEN VALLEY IS THE OWNER PERMITTEE APPLYING FOR PERMIT COVERAGE AND WILL BE RESPONSIBLE FOR DEVELOPING THIS SWPPP AND THE LONG-TERM MAINTENANCE PLAN OF THE PERMANENT STORMWATER MANAGEMENT SYSTEM FOR THIS PROJECT (IF APPLICABLE). THE OWNER WILL ENSURE THAT THE DESCRIBED WORK IN THE SWPPP IS BEING COMPLETED BY THE OPERATOR PERMITTEE.

OWNER/PERMITTEE: CITY OF GOLDEN VALLEY (ERIC ECKMAN)
 7800 GOLDEN VALLEY ROAD
 GOLDEN VALLEY, MN 55427
 763-593-8084/ECKMAN@GOLDENVALLEYMN.GOV

THE PRIMARY CONTRACTOR WILL ENTER INTO A CONTRACT WITH THE CITY OF GOLDEN VALLEY TO COMPLETE THE REQUIRED WORK FOR THIS PROJECT. THE PRIMARY CONTRACTOR WILL BECOME (UNDER CONTRACT) THE OPERATOR CO-PERMITTEE ON THE NPDES PERMIT (THROUGH EXECUTION OF A NPDES PERMIT MODIFICATION FORM), AND THEREBY AGREE TO IMPLEMENT THIS SWPPP IN COOPERATION WITH THE OWNER. THE OPERATOR IS RESPONSIBLE FOR DEVELOPING A CHAIN OF RESPONSIBILITY PRIOR TO STARTING CONSTRUCTION (REFER TO SWPPP AMENDMENT SECTION). THE NPDES PERMIT MODIFICATION FORM SHALL BE SUBMITTED TO THE MPCA AFTER THE PROJECT IS AWARDED TO THE PRIMARY CONTRACTOR, PRIOR TO LETTING THE PROJECT.

THE OPERATOR WILL INSURE THAT INDIVIDUALS OVERSEEING OR IMPLEMENTING THE SWPPP HAVE BEEN PROPERLY TRAINED AND THAT CERTIFICATIONS WILL BE MADE AVAILABLE UPON REQUEST. THIS INCLUDES ANY SUB-CONTRACTORS THAT THE OPERATOR EMPLOYS UNDER SEPARATE CONTRACT. THE OPERATOR WILL PROVIDE THE CONTACT INFORMATION FOR THE EROSION CONTROL SUPERVISOR, SITE SUPERINTENDENT/FOREMAN, AND BMP INSTALLERS. THE EROSION CONTROL SUPERVISOR SHALL BE A RESPONSIBLE EMPLOYEE OF THE PRIME CONTRACTOR AND/OR DULY AUTHORIZED BY THE PRIME CONTRACTOR TO REPRESENT THE PRIME CONTRACTOR ON ALL MATTERS PERTAINING TO THE NPDES CONSTRUCTION STORMWATER PERMIT COMPLIANCE. THE EROSION CONTROL SUPERVISOR SHALL HAVE AUTHORITY OVER ALL OPERATOR OPERATIONS WHICH INFLUENCE NPDES PERMIT COMPLIANCE, INCLUDING GRADING, EXCAVATION, CULVERT INSTALLATION, CLEARING/GRUBBING, DEWATERING, AND ANY OTHER OPERATION THAT INCREASES THE EROSION POTENTIAL ON THE PROJECT.

THE OPERATOR WILL PERFORM A PRECONSTRUCTION SITE VISIT TO ADDRESS ANY AREAS OF CONCERN PERTAINING TO ENVIRONMENTAL COMPLIANCE. THE OPERATOR WILL IMPLEMENT AND MAINTAIN BMPS FOR THE DURATION OF CONSTRUCTION PROJECT. THE OPERATOR WILL COMPLETE THE REQUIRED SITE INSPECTIONS TO REMAIN IN COMPLIANCE WITH NPDES PERMIT REQUIREMENTS PART II.B, II.C, III.B-F, IV, V, AND APPLICABLE CONSTRUCTION ACTIVITY REQUIREMENTS FOUND IN APPENDIX A, PART C.

OPERATOR/PERMITTEE: (TO BE DETERMINED THROUGH TRANSFER OF NPDES-CSW PERMIT)

WSB & ASSOCIATES HAS BEEN CONTRACTED BY THE OWNER TO DEVELOP THE SWPPP PLAN FOR THIS PROJECT. THIS SWPPP WAS PREPARED BY AN INDIVIDUAL THAT HAS BEEN PROPERLY TRAINED IN ACCORDANCE TO PART III.F OF THE NPDES PERMIT (CERTIFICATION CARDS ARE AVAILABLE UPON REQUEST). WSB & ASSOCIATES WILL OFFER GUIDANCE FOR COMPLIANCE WITH THE NPDES PERMIT BEFORE, DURING, AND AFTER CONSTRUCTION OF THE PROJECT.

SWPPP DEVELOPER: WSB & ASSOCIATES, INC. (GREG BECKIUS)
 477 TEMPERANCE STREET
 ST. PAUL, MN 55101
 651-286-8468/GBECKIUS@WSBENG.COM

WATER RESOURCE ENGINEER: WSB & ASSOCIATES, INC. (JOEY ABRAMSON)
 701 XENIA AVE. SOUTH, SUITE 300
 MINNEAPOLIS, MN 55416
 763-270-3469/JABRAMSON@WSBENG.COM

AGENCY CONTACTS			
AGENCY	PERMIT	NAME	PHONE NUMBER/E-MAIL
MPCA (EMERGENCY)	N/A	STATE DUTY OFFICER	1-800-422-0798
MPCA	NPDES-CSW #C000XXXXX	BRANDON DAHL	651-757-2279/BRANDON.DAHL@STATE.MN.US
ACOE	SECTION 404	N/A	651-290-5525
MN DNR	PUBLIC WATERS WORK PERMIT	N/A	651-296-6157
BASSETT CREEK WATERSHED MANAGEMENT COMMISSION	EROSION CONTROL	JIM HERBERT	952-832-2784

PROJECT DESCRIPTION & SCHEDULE

THE BASSETT CREEK RESTORATION PROJECT CONSISTS OF STREAM BANK RESTORATION TO TWO AREAS OF THE MAIN STEM OF BASSETT CREEK. AREA A IS LOCATED BETWEEN WISCONSIN AVENUE, JUST NORTH OF HIGHWAY 55, AND EXTENDS EAST 2,100 FEET TO 10TH STREET, JUST PAST WINNETKA AVE. THE SECOND AREA IS LOCATED NORTH OF DULUTH STREET, JUST WEST OF HIGHWAY 100, AND EXTENDS NORTH 4,000 FEET, TO THE GOLDEN VALLEY/CRYSTAL BORDER. THE DESIGNED STABILIZATION MEASURES FOR THE PROPOSED PROJECT WILL INCLUDE MAINTAINING THE CHANNELIZATION OF THE CREEK BY IMPLEMENTING THE FOLLOWING: REMOVE TREES THAT ARE LEANING OVER AND LIKELY TO FALL INTO THE CREEK, SHAPE ERODED SLOPES IN SELECTED AREAS OF THE CREEK TO PROVIDE A

SUSTAINABLE SLOPE AND TO SUPPORT IMPROVED VEGETATION GROWTH, REPLACE AND INSTALL NEW STORM SEWER OUTFALLS THAT DISCHARGE INTO THE CHANNEL TO PREVENT FURTHER DAMAGE AND EROSION, AND ESTABLISH NATIVE VEGETATION ALONG DISTURBED STREAM BANKS.

TENTATIVE CONSTRUCTION SCHEDULE (OPERATOR SHOULD PROVIDE ESTIMATED CONSTRUCTION SCHEDULE TO THE ENGINEER)	
CONSTRUCTION ACTIVITIES:	ESTIMATED DATES OF SOIL DISTURBANCE ACTIVITIES:
CLEARING AND GRUBBING OPERATIONS, GRADING	JUNE - NOVEMBER 2015
INITIAL TURF	NOVEMBER 2015
LANDSCAPING, FINAL TURF, MISC.	NOVEMBER 2015

PRE-CONSTRUCTION IMPERVIOUS SURFACE AND DISTURBED AREA CALCULATIONS

TOTAL AREA TO BE DISTURBED = 2.25 ACRES
 IMPERVIOUS AREA: PRE-CONSTRUCTION = 0.00 ACRES/POST-CONSTRUCTION = 0.00 ACRES
 NET INCREASE OF IMPERVIOUS AREA = 0.00 ACRES

PERMANENT STORMWATER MANAGEMENT SYSTEMS

THE NPDES DOES NOT REQUIRE PERMANENT WATER QUALITY VOLUME CONTROL (PART III.D) FROM THE NET NEW IMPERVIOUS SURFACES BECAUSE THE NET INCREASE IS LESS THAN ONE ACRE.

LOCATION OF SWPPP COMPONENTS		
DESCRIPTION	TITLE	LOCATION
SWPPP NARRATIVE	STORMWATER POLLUTION PREVENTION PLAN NARRATIVE	PLAN SET
SITE CONDITIONS	STORMWATER POLLUTION PREVENTION PLAN NARRATIVE	PLAN SET
SITE MAP (SOILS, WATER RESOURCES, POTENTIAL POLLUTANT GENERATING ACTIVITIES)	SWPPP WATER RESOURCES & SOILS MAP, SWPPP NARRATIVE	PLAN SET
CONSTRUCTION PHASING/STAGING, BUFFERS, & AREAS NOT TO BE DISTURBED	SWPPP NARRATIVE	PLAN SET
DIRECTION OF FLOW (PRE- & POST-CONSTRUCTION)	DRAINAGE PLAN	PLAN SET
IMPERVIOUS SURFACES	CONSTRUCTION PLAN & PROFILE	PLAN SET
TEMPORARY EROSION & SEDIMENT CONTROL BMPS/STEEP SLOPES (3:1), DNR FISH EXCLUSION "WORK IN WATER RESTRICTIONS- REFER TO SWPPP"	TEMPORARY EROSION AND SEDIMENT CONTROL PLAN, SWPPP NARRATIVE	PLAN SET
PERMANENT EROSION CONTROL BMPS	TURF ESTABLISHMENT PLAN, SWPPP NARRATIVE	PLAN SET
STORM SEWER	DRAINAGE PLAN	PLAN SET
GRADING	GRADING PLAN	PLAN SET
ESTIMATED BMP QUANTITIES	ESTIMATED QUANTITIES	PLAN SET
BMP DETAILS/SPECIFICATIONS	MISC. DETAILS, SWPPP NARRATIVE	PLAN SET
HYDROLOGIC/WATER QUALITY MODELING		AVAILABLE UPON REQUEST

EXISTING SITE CONDITIONS, SOILS, & WATER RESOURCES

SOILS AND NATIVE TOPSOIL: NATIVE TOPSOIL WILL BE STRIPPED AND STOCKPILED FOR FINAL GRADING OPERATIONS, WHERE INDICATED IN THE CONSTRUCTION PLANS AND SPECIFICATIONS. METHODS AND EQUIPMENT TO MINIMIZE SOIL COMPACTION (IN PROPOSED INFILTRATION AREAS, DRIP LINE OF TREES TO BE PRESERVED, ETC.) SHALL BE DETERMINED BY THE OPERATOR'S SWPPP AMENDMENT. TRACKED VEHICLES ARE PREFERRED AND WHEELED VEHICLES ARE DISCOURAGED IN THESE AREAS.

THE FOLLOWING USDA-NRCS MAPPED SOILS ARE SHOWN AS "NOT HIGHLY ERODIBLE LAND", "POTENTIALLY HIGHLY ERODIBLE LAND", AND "HIGHLY ERODIBLE LAND" ON THE SWPPP SITE MAP.

USDA-NRCS MAPPED SOIL SURVEY UNIT NO., NAME, TEXTURE, SLOPE PERCENTAGE	APPROXIMATE PARTICLE SIZE RANGE (MM)		
	SAND (0.05-2.00+)	SILT (0.002-0.05)	CLAY (<0.002)
L2B - MALARDI-HAWICK COMPLEX, 1-6% SLOPES	50-70%	0-50%	15-20%
L2C - MALARDI-HAWICK COMPLEX, 6-12% SLOPES	50-70%	0-50%	15-20%
L2D - MALARDI-HAWICK COMPLEX, 12-18% SLOPES	50-70%	0-50%	15-20%
L6A - BISCAY CLAY LOAM, 0-2% SLOPES	20-45%	15-52%	27-40%
L30A - MEDO SOILS, DEPRESSIONAL, 0-1% SLOPES	N/A	N/A	N/A
U1A - URBAN LAND-UDORTHENTS, WET SUBSTRATUM, COMPLEX, 0-2% SLOPES	N/A	N/A	N/A

DESCRIPTION OF RECEIVING WATERS (LOCATED WITHIN 1-MILE): STORMWATER FROM THIS PROJECT WILL DISCHARGE DIRECTLY TO BASSETT CREEK. STORMWATER RUNOFF IS FILTERED THROUGH THE VEGETATED SIDE SLOPES BEFORE SHEET FLOWING INTO THE CREEK. HYDROLOGIC AND WATER QUALITY MODELING DATA IS AVAILABLE UPON REQUEST.

DESCRIPTION OF IMPAIRED WATERS OR WATER SUBJECT TO TMDLS: A SPECIAL AND IMPAIRED WATERS SEARCH WAS COMPLETED USING THE MPCA SEARCH ENGINE (HTTP://PCA-GIS02.PCA.STATE.MN.US/CSW/INDEX.HTML) ON 05/21/2015. BASED ON THIS REVIEW, THE FOLLOWING SPECIAL OR IMPAIRED WATERS (WITH CONSTRUCTION RELATED IMPAIRMENTS) ARE LOCATED WITHIN ONE MILE OF, AND DOWNSTREAM OF ANY PROJECT DISCHARGE POINTS: BASSETT CREEK (AUID 07010206-538) IS IMPAIRED (CHLORIDE, FECAL COLIFORM, FISH BIOASSESSMENT), THEREFORE MPCA CGP APPENDIX A REQUIREMENTS APPLY TO THIS PROJECT.

STORM WATER POLLUTION PREVENTION PLAN

CITY PROJECT NUMBER 13-25
 PROJECT NUMBER 02032-09

- SEDIMENT AND FUGITIVE DUST GENERATED FROM CLEARING AND GRUBBING, IMPORT/EXPORT OPERATIONS, REMOVALS/COMPACTION, MASS/FINE GRADING, EXCAVATIONS, TRENCHING, TOPSOIL STRIPING STOCKPILING, WET/DRY PAVEMENT CUTTING, STREET CONSTRUCTION.
- BASIC/ACIDIC PH LEVELS FROM CURB AND GUTTER, MANHOLE STRUCTURES, SIDEWALKS, DRIVEWAY APRONS, FOUNDATIONS, BRIDGE ABUTMENTS, WET/DRY PAVEMENT CUTTING, MASONRY WASHOUT/CLEANOUT.
- EXCESS NUTRIENTS FROM LANDSCAPING INSTALLATIONS, SOIL ADDITIVES, FERTILIZATION, MULCHING
- HYDROCARBONS FROM STREET CONSTRUCTION, DEMOLITION/REMOVALS, WET/DRY PAVEMENT CUTTING

OPERATOR WILL COMPLY WITH ALL OF THE POLLUTION PREVENTION AND MANAGEMENT MEASURES IDENTIFIED IN THE NPDES-CSW PERMIT. OPERATOR WILL SUBMIT A SPILL PREVENTION AND RESPONSE PLAN (SPRP) TO THE ENGINEER PRIOR TO ANY CONSTRUCTION ACTIVITY. THE SPRP MUST SATISFACTORILY ADDRESS (AT A MINIMUM) THE FOLLOWING NPDES REQUIREMENTS BY THE PROPOSED IMPLEMENTATION AND MAINTENANCE OF APPROPRIATE BMPS:

NO-EXPOSURE: CONSTRUCTION AND BUILDING PRODUCTS (THAT HAVE THE POTENTIAL TO LEACH POLLUTANTS), PESTICIDES, HERBICIDES, INSECTICIDES, FERTILIZERS, TREATMENT CHEMICALS, AND LANDSCAPING MATERIALS MUST BE UNDER COVER (PLASTIC SHEETING OR TEMPORARY ROOFS) TO MINIMIZE CONTACT WITH STORMWATER AND PRECIPITATION.

SOLID WASTE: (SEDIMENT, ASPHALT, CONCRETE MILLINGS, CONSTRUCTION, AND DEMOLITION DEBRIS) AND OTHER WASTES MUST BE DISPOSED OF PROPERLY AND SHALL COMPLY WITH MPCA DISPOSAL REQUIREMENTS (CH. 7035).

HAZARDOUS MATERIALS: (E.G. GAS, DIESEL, OIL, ANTIFREEZE, PAINT SOLVENTS, SOAPS, DETERGENTS, WOOD PRESERVATIVES, CLEANING SOLVENTS, CURING COMPOUNDS, ACIDS, ETC.) MUST BE STORED IN SEALED CONTAINERS (WITH SECONDARY SPILL CONTAINMENT) IN RESTRICTED ACCESS AREAS TO PREVENT VANDALISM. STORAGE AND DISPOSAL OF HAZARDOUS WASTES AND MATERIALS MUST BE IN COMPLIANCE WITH MPCA REGULATIONS (CH. 7045) INCLUDING SECONDARY CONTAINMENT.

PORTABLE TOILETS: MUST BE POSITIONED AND SECURED SO THEY ARE NOT TIPPED OR KNOCKED OVER.

EQUIPMENT/VEHICLE FUELING, EXTERNAL WASHING, AND MAINTENANCE PRACTICES: ALL EQUIPMENT OPERATING WITHIN BASSETT CREEK CONSIST OF BIODEGRADABLE SUBSTANCES. WHEN VEHICLE FUELING, MAINTENANCE, OR EXTERNAL WASHING MUST OCCUR ON-SITE, THE ACTIVITY IS LIMITED TO A CONTAINED PORTION OF THE STAGING AREA, UNLESS INFEASIBLE THROUGH A SWPPP AMENDMENT. PROCEDURES FOR SPILL RESPONSE AND MATERIALS FOR CONTAINMENT AND CLEAN UP (DRIP PANS, DRY ABSORBENTS, AND SPILL KITS) WILL BE AVAILABLE AT ALL TIMES ON-SITE. ENGINE DEGREASING IS PROHIBITED ON-SITE.

CONCRETE, STUCCO, PAINT, CURING COMPOUNDS, SOLVENTS, AND OTHER WASHOUT WASTES: TEMPORARY OR LONG-TERM STORAGE OF WASHOUT WASTE IS PROHIBITED ON-SITE (SLURRY MUST BE HAULED IMMEDIATELY OFF-SITE). OPERATOR MUST SUBMIT A CONCRETE WASHOUT PLAN TO THE PROJECT ENGINEER FOR APPROVAL OF ALL ON-SITE WASHOUT LOCATIONS. ON-SITE WASHOUT LOCATIONS MUST BE LOCATED 200 FEET FROM AN ENVIRONMENTALLY SENSITIVE AREA AND SURFACE WATERS, HAVE "CONCRETE WASHOUT AREA" SIGNAGE, AND BE CONTAINED IN A LEAK PROOF CONTAINER OR IMPERMEABLE LINER. LIQUID AND SOLID WASTES SHOULD NOT CONTACT THE GROUND (UNLESS PERMITTED IN THE CONCRETE WASHOUT PLAN), BE CONTAINED TO PREVENT RUNOFF FROM THE WASHOUT LOCATION, AND MUST BE DISPOSED OF PROPERLY AND IN COMPLIANCE WITH MPCA REGULATIONS.

BURNING: BURNING OF GARBAGE, CONSTRUCTION DEBRIS, TREES, BRUSH, OR OTHER VEGETATIVE MATERIAL IS NOT ALLOWED ON SITE, UNLESS PRIOR APPROVAL IS GRANTED BY THE OWNER.

EROSION CONTROL PRACTICES, PROCEDURES, & MAINTENANCE STANDARDS

THE OPERATOR IS RESPONSIBLE FOR THE INSTALLATION, OPERATION, AND CONTINUED MAINTENANCE OF ALL TEMPORARY AND PERMANENT WATER QUALITY MANAGEMENT BMPS, AS WELL AS ALL EROSION PREVENTION AND SEDIMENT CONTROL BMPS, FOR THE DURATION OF THE CONSTRUCTION WORK AT THE SITE, UNTIL FINAL STABILIZATION IS ACHIEVED. ALL BMPS MUST BE ADEQUATELY LOCATED, DESIGNED, INSTALLED, AND MAINTAINED TO PREVENT EROSION FROM A MINIMUM 0.5 INCH TOTAL RAINFALL EVENT WITHIN 24 HOURS.

ALL NONFUNCTIONAL BMPS MUST BE REPAIRED, REPLACED, OR SUPPLEMENTED WITH FUNCTIONAL BMPS BY THE END OF THE NEXT BUSINESS DAY AFTER DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS UNLESS ANOTHER TIME FRAME IS SPECIFIED IN THE SWPPP. ALL ERODED MATERIAL THAT LEAVES THE SITE SHALL BE COLLECTED BY THE OPERATOR AND RETURNED TO THE SITE AT THE OPERATOR'S EXPENSE AND INCIDENTAL TO THE PROJECT COST.

TEMPORARY OR PERMANENT STABILIZATION SHALL BE INITIATED AS SOON AS POSSIBLE, BUT NO LATER THAN THE END OF THE NEXT WORK DAY FOLLOWING THE DAY EARTH-DISTURBING ACTIVITIES IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. ALL EXPOSED SOIL AREAS SHALL BE STABILIZED WITHIN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. INITIATED STABILIZATION IS DEFINED AS COMPLETING ONE (OR MORE) OF THE FOLLOWING: SOIL PREPARATION FOR VEGETATION, MULCHING (OR OTHER TEMPORARY NON-VEGETATIVE BMP), SEEDING/PLANTING, OR SCHEDULING STABILIZATION MEASURES TO BE FULLY INSTALLED AND COMPLETED WITHIN THE 7 DAY TIMEFRAME.

ALL EXPOSED SOILS WITHIN 200 FEET AND DRAINING TO A DNR PUBLIC WATERS MUST BE STABILIZED WITHIN 24 HOURS OF TEMPORARILY OR PERMANENTLY CEASING WORK, DURING THE FISH SPAWNING PERIOD. TEMPORARY STOCKPILES WITHOUT SIGNIFICANT SILT, CLAY OR ORGANIC COMPONENTS (E.G., CLEAN AGGREGATE STOCKPILES, DEMOLITION CONCRETE STOCKPILES, SAND STOCKPILES) AND THE CONSTRUCTED BASE COMPONENTS OF ROADS, PARKING LOTS AND SIMILAR SURFACES ARE EXEMPT FROM THIS REQUIREMENT.

TEMPORARY STABILIZATION BMPS SHALL ONLY BE IMPLEMENTED WHEN PERMANENT STABILIZATION BMPS CANNOT BE IMPLEMENTED WITHIN THE 7 DAY TIMEFRAME FOR EXPOSED SOILS.

TEMPORARY/PERMANENT DRAINAGE DITCHES & SWALES: THE NORMAL WETTED PERIMETER (2-YEAR, 24-HOUR PRECIPITATION EVENT) OF ANY TEMPORARY OR PERMANENT DRAINAGE DITCH, CHANNEL, OR SWALE THAT DRAINS WATER FROM ANY PORTION OF THE CONSTRUCTION SITE, OR DIVERTS WATER AROUND THE SITE, MUST BE STABILIZED WITHIN THE LAST 200 LINEAL FEET FROM THE PROPERTY EDGE, OR FROM THE POINT OF DISCHARGE INTO ANY SURFACE WATER WITHIN 24 HOURS OF CONNECTION. STABILIZATION REMAINING OF THE REMAINING PORTIONS OF THE CHANNEL MUST BE STABILIZED WITHIN 7 DAYS. ALL STORMWATER CONVEYANCE CHANNELS MUST USE EROSION CONTROL AND VELOCITY DISSIPATION DEVICES WITHIN AND ALONG THE LENGTH OF THE CHANNEL AND AT ANY OUTLETS. TEMPORARY OR PERMANENT DITCHES OR SWALES THAT ARE BEING USED AS A TEMPORARY SEDIMENT CONTAINMENT SYSTEM (WITH PROPERLY DESIGNED ROCK DITCH CHECKS, BIO ROLLS, SILT DIKES ETC.) DO NOT NEED TO BE STABILIZED. THESE AREAS MUST BE STABILIZED WITHIN 24 HOURS AFTER NO LONGER BEING USED AS A SEDIMENT CONTAINMENT SYSTEM. MULCH, HYDROMULCH,

TACKIFIER, OR POLYARCRYLAMIDE BELOW THE WETTED PERIMETER OF A DITCH, SWALE, OR OTHER SURFACE WATER CONVEYANCE IS NOT ACCEPTABLE STABILIZATION.

EROSION CONTROL BLANKETS/MATS: OPERATOR SHALL VERIFY DURING REGULAR INSPECTIONS THAT NO GULLIES, RILLS, OR SCOUR HOLES HAVE FORMED UNDER EROSION CONTROL BLANKETS AND MATS. ALL REPAIRS MUST BE COMPLETED WITHIN 24 HOURS OF DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS.

MULCH: OPERATOR MUST APPLY MULCH IN A UNIFORM PATTERN OVER THE DISTURBED SOILS, TO ACHIEVE A MINIMUM OF 90% GROUND COVER.

DUST CONTROL: DUST FROM THE SITE WILL BE CONTROLLED BY INCREASED STREET SWEEPING AND/OR USING A MOBILE PRESSURE-TYPE DISTRIBUTOR TRUCK TO APPLY POTABLE WATER TO DISTURBED AREAS. THE MOBILE UNIT WILL APPLY WATER AT A RATE NECESSARY TO PREVENT RUNOFF AND PONDING.

STORM SEWER OUTLETS: PIPE OUTLETS MUST HAVE TEMPORARY OR PERMANENT ENERGY DISSIPATION WITHIN 24 HOURS AFTER HYDRAULIC CONNECTION TO A RECEIVING SURFACE WATER.

TEMPORARY & PERMANENT EROSION CONTROL BMPS

RAPID STABILIZATION METHOD #4: THIS METHOD SHALL CONSIST OF CATEGORY 3 EROSION CONTROL BLANKET (NATURAL NET ONLY) IN COMBINATION WITH MNDOT SEED MIX 22-111 (2 LBS PER 100 SQ. YD.) AND TYPE 3 SLOW RELEASE FERTILIZER (8 LBS PER 100 SQ. YD.) IS AN ACCEPTABLE BMP FOR DISTURBED AREAS ADJACENT TO ENVIRONMENTALLY SENSITIVE AREAS, SURFACE WATERS, AND WITHIN THE LAST 200 FEET OF DITCH BOTTOMS.

SOD/SEED MIX: MNDOT SEED MIX AND/OR SOD WITH APPROPRIATE MNDOT FERTILIZER WILL BE USED AS PERMANENT COVER FOR ALL EXPOSED GROUND AREAS PER MANUFACTURERS SPECIFICATIONS.

EROSION CONTROL BLANKET: A MNDOT CLASSIFIED EROSION CONTROL BLANKET SHALL BE ADDED IN COMBINATION WITH SEED MIX/FERTILIZER TO ALL AREAS SLOPED AT 3:1 OR GREATER, HIGH PRIORITY AREAS, AS WELL AS IN OR NEAR DITCH BOTTOMS TO ESTABLISH PERMANENT EROSION CONTROL.

TEMPORARY WINTER COVER: AREAS OF EXPOSED SOILS THAT ARE NOT COMPLETED BEFORE THE WINTER WILL BE STABILIZED WITH TYPE #3 (CERTIFIED AS WEED FREE) ADJACENT TO WETLAND OR STORMWATER PONDS. ALL OTHER DISTURBED AREAS SHALL BE STABILIZED WITH TYPE #1 MULCH, UNLESS ALTERNATIVE MORE PROTECTIVE BMPS ARE SPECIFIC WITHIN THE SWPPP. ALL EXPOSED SOILS SHALL BE STABILIZED BEFORE CONSTRUCTION IS COMPLETED FOR THE SEASON.

SEDIMENT CONTROL PRACTICES, PROCEDURES, & MAINTENANCE STANDARDS

DOWN GRADIENT SYSTEMS: IF THE DOWN GRADIENT TREATMENT SYSTEM IS OVERLOADED, ADDITIONAL UP GRADIENT SEDIMENT CONTROL PRACTICES OR REDUNDANT BMPS MUST BE INSTALLED TO ELIMINATE THE OVERLOADING, AND THE SWPPP MUST BE AMENDED TO IDENTIFY THESE ADDITIONAL PRACTICES.

PERIMETER CONTROL BMPS (SILT FENCES, CHIP/SLASH MULCH SACKS, BIOROLLS, FLOATING SILT CURTAIN, ETC.): PERIMETER CONTROL BMPS SHALL BE INSTALLED ON ALL DOWN GRADIENT PERIMETERS AND UPGRADIENT OF ANY BUFFER AREAS, PRIOR TO INITIATING UPGRADIENT LAND DISTURBANCE ACTIVITIES. UPLAND PERIMETER CONTROLS BMPS SHALL BE PLACED AS CLOSE AS POSSIBLE TO FOLLOW A SINGLE CONTOUR ELEVATION. ALL SILT FENCES MUST BE REPAIRED, REPLACED, OR MAINTAINED WHEN THEY BECOME NONFUNCTIONAL OR THE SEDIMENT REACHES 1/2 OF THE HEIGHT OF THE FENCE. ALL REPAIRS MUST BE COMPLETED BY THE END OF THE NEXT BUSINESS DAY AFTER DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS. FLOATING SILT CURTAIN SHALL BE INSTALLED AS CLOSE TO THE SHORELINE AS POSSIBLE FOR SHORELAND/IN-WATER SHORT-TERM CONSTRUCTION ACTIVITIES. AFTER THE SHORT-TERM ACTIVITY IN COMPLETE, AN UPLAND PERIMETER CONTROL MUST BE INSTALLED IF EXPOSED SOILS CONTINUE TO DRAIN TO THE SURFACE WATER.

50 FOOT NATURAL BUFFER(S): REFER TO "CONSTRUCTION PHASING/STAGING, BUFFERS, & AREAS NOT TO BE DISTURBED" SECTION OF THIS SWPPP.

TEMPORARY SEDIMENTATION BASINS: WHERE TEN (10) OR MORE ACRES OF DISTURBED SOIL DRAIN TO A COMMON LOCATION, A TEMPORARY SEDIMENT BASIN MUST BE PROVIDED PRIOR TO RUNOFF LEAVING THE CONSTRUCTION SITE OR ENTERING SURFACE WATERS. ALL TEMPORARY BASINS SHALL BE CONSTRUCTED AND OPERATIONAL PRIOR TO GRADING TEN (10) OR MORE ACRES. BASINS MUST PROVIDE A LIVE STORAGE VOLUME FROM A TWO YEAR 24-HOUR STORM EVENT FROM EACH ACRE (DISTURBED AND UNDISTURBED) DRAINING TO THE BASIN. AT A MINIMUM, IF CALCULATIONS ARE NOT PERFORMED THE BASIN SHALL PROVIDE 3,600 CUBIC FEET OF LIVE STORAGE FROM EACH ACRE. THE BASIN INTAKE MUST BE DESIGNED TO WITHDRAW WATER FROM THE SURFACE, PREVENT SHORT CIRCUITING AND THE DISCHARGE OF FLOATING DEBRIS, INCLUDE AN EMERGENCY OVERFLOW ABOVE THE LIVE STORAGE ELEVATION, AND PROVIDE ENERGY DISSIPATION AT THE BASIN OUTLET. BASINS MUST BE DRAINED AND SEDIMENT REMOVED WHEN THE DEPTH OF COLLECTED SEDIMENT IN THE BASIN REACHES 1/2 THE LIVE STORAGE VOLUME. DRAINAGE AND REMOVAL MUST BE COMPLETED WITHIN 72 HOURS OF DISCOVERY, OR AS SOON AS FIELD CONDITIONS ALLOW ACCESS. IF A BASIN IS INFEASIBLE WITHIN THE PROJECT LIMITS, EQUIVALENT SEDIMENT CONTROL BMPS MUST BE IMPLEMENTED AND DOCUMENTED IN THE SWPPP OR SWPPP AMENDMENT.

TEMPORARY STOCKPILES: ALL STOCKPILES MUST HAVE SILT FENCE OR EQUIVALENT PERIMETER SEDIMENT CONTROLS IMPLEMENTED AND MAINTAINED AT ALL TIMES. PILES CANNOT BE PLACED IN BUFFER AREAS OR SURFACE WATERS, INCLUDING STORMWATER CONVEYANCES SUCH AS CURB AND GUTTER SYSTEMS, OR CONDUITS AND DITCHES UNLESS THERE IS A BYPASS IN PLACE TO PREVENT STORMWATER RUN-ON INTO THE STOCKPILE.

CONSTRUCTION SITE ENTRANCE/VEHICLE TRACKING: OPERATOR MUST MINIMIZE SEDIMENT FROM LEAVING THE CONSTRUCTION SITE (OR ONTO STREETS WITHIN THE SITE) BY IMPLEMENTING BMPS SUCH AS ROCK PADS, SLASH MULCH, CONCRETE OR STEEL WASH RACKS, OR EQUIVALENT SYSTEMS. STREET SWEEPING MUST BE USED DAILY DURING CONSTRUCTION OPERATIONS IF SUCH BMPS ARE NOT ADEQUATE TO PREVENT SEDIMENT FROM BEING TRACKED ONTO THE STREET. TRACKED SEDIMENT MUST BE REMOVED FROM ALL PAVED SURFACES (ON AND OFF-SITE) WITHIN 24 HOURS OF DISCOVERY, OR SOONER AS DIRECTED BY THE PROJECT OWNER. MULTIPLE STREET SWEEPINGS AT THE OPERATOR'S EXPENSE MAY BE REQUIRED ON ALL ENTRY/EXIT POINTS TO THE SITE AT THE DISCRETION OF THE PROJECT OWNER.

STORM WATER POLLUTION PREVENTION PLAN

CITY PROJECT NUMBER 13-25
PROJECT NUMBER 02032-09

REVISION NO. DATE	AS NOTED	DESIGN BY: JHA	PROJECT NO: 02032-09	DATE
	SCALE: PLAN BY: JHA	CHECKED BY: PRW	RECORD COPY BY:	
	I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY CLOSE PERSONAL SUPERVISION AND THAT I AM A FULLY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MINNESOTA.			
	PETER R. WILLENBRING, PROFESSIONAL ENGINEER DATE: _____ LIC. NO. 15998			
2015 MAIN STEM OF BASSETT CREEK RESTORATION PROJECT CITY OF GOLDEN VALLEY				
701 Xenia Avenue South, Suite 300 Minneapolis, MN 55416 www.wsbg.com				
763-541-8800 • Fax 763-541-1700 INFRASTRUCTURE ENGINEERING PLANNING CONSTRUCTION				

K:\02032-090\Cad\Proposed\02032-090 - Edgewood Storm.dwg

